



This was copied from the book he mentions
just at the time of his death Feb 13 - 1945
He was my cousin Wm. Farrey son of Wm. Farrey
Turners Falls - and worked for the Atlas Powder
Co - Tamaqua Pa.

In my early days in Tamaqua
Penn. ^{in the 1920s} I lived with four
other men in the club house
furnished by the Atlas Powder
Co.

Weather permitting on Sunday
afternoons we took walks
out into the country and
often ran into the ruins of
Black Powder Mills which in
previous days had supplied
the many Anthracite Coal mines
in the neighborhood.

^{It was} ~~from~~ from the owner of one
of these mines that I obtained
the Book from which I'm
^{going} about to quote ^{the} information
given about the Hoosier Tunnel.

When this man died his
widow in accordance with
the custom at that time sold
off his effects

2) a friend of mine who was a neighbor bought several Books among which one being a

Treatise on Explosive Compounds
Machine Rock Drills and
Blasting by Henry S Drinkier
EM a graduate of the
Lehigh School of Mines and
author of several Books on
Tunnels. covering the Hessian Tunnel
The Book was published in
1883 by John Wiley & Sons
New York.

As a foreword to the description
of the Hessian Tunnel Mr Drinkier
advises that he obtained his
information from the Files of
Mass State Engineers ~~and~~ the
the Mass legislative Reports
~~and~~ Mass state library etc. as
well as other sources

It seems apparent that he made

3) These latter included the Records of the Contractors and Engineers particularly Mr Walter Shanley and others too numerous to mention.

IT is apparent that this is a very complete and accurate account of the Construction of the Tunnel.

He admittedly eliminated some of the details on financing etc and I will eliminate additional information that I do not think of interest.

Mr Drinnier in starting this study pointed out that as early as 1825 They ^{considered} tunnelling Hoosac Mt to provide a water way from Boston to the Hudson by means in part of the Deerfield and Hoosac Rivers.

The proposal was found to be practical but shortly thereafter

4) Railroads came into favor so
the ^{waterway} plan was dumped.

In 1848 an application was
made for a charter to build
a Railroad from Greenfield
through the Deerfield and Hoosac
Valleys to connect with a
railroad leading to Troy New York.
A charter was granted limiting
the stock to 3 1/2 Million Dollars.

In 1854 the Mass. legislature
granted the Troy and Greenfield
Railroad Co. a permission to
build a Tunnel through the
Hoosac Mt ~~at a cost not to~~
~~exceed~~ and lent credit to
the amount of 2 Million Dollars.

On the basis of labor and
material costs at that time
a Tunnel 24 ft wide, 20 ft high
arched at the top and 24100 ft ^{4 1/2}
long could be built for
this amount.

5) Working from both ends or
2 faces the time required
was estimated at 1556 Days.
If it was decided to sink a
shaft from the top of the Mt
to the Mid Point of the Tunnel
thus creating 2 more faces the
time would be reduced to
1054 days. ~~4 1/2~~ approx 4 1/2 + 3
years ^{respec}

In 1855 a contract was made
with E W Serrel & Co to ~~complete~~
~~the~~ ^{to} build a road to the
Tunnel site.

This contract fell thru and was
assumed by H. Haupt & Co. in 1858
they were to receive 2 Million \$
in Mass Bonds, \$900,000 in
Mortgage Bonds of the Company
and \$1,100,000 in Cash.
Work was started but
discontinued in July 1861 due to
a controversy over the method of
payment.

J) The air was delivered to the face thru an 8" pipe.

This pipe was laid in a ~~channel~~ channel in the bottom of the Tunnel.

which ~~also~~ besides serving as a drain for the water encountered provided room for a 3" pipe for ~~ventilation~~ water for the drills

and a 4" pipe for Gas for lighting and a 12" pipe for air for ventilation

until this time Candles were used as the source of light and were listed as an essential part of the costs.

As an example one estimation showed the use of 2000 lbs of Candles over a period of 7 months.

On Jan 1 1864 the ~~central~~ shaft elliptical in shape 27 x 15 ft was started at the top of the mountain above the midpoint of the Tunnel.

This ~~was completed~~ reached the tunnel grade on Aug 13 1870 - about 7 1/2 years later - the work being completed by the Shanley Constructch Co.

8) In 1866 under the supervision of Mr. Doane the Chief Engineer Experiments were completed with Nitroglycerin.

This product was not invented by Nobel but he discovered and held the Patents on its use as a Blasting Agent.

Thru licenses and joint ownerships of plants through out the world Nobel accumulated the Fortune which was the basis of the Nobel Prizes for Peace and other endeavors.

In 1966 progress at the rate of 96 ft per month was ^{made} ~~experimented~~ at the East Portal, but due to a difference in the Rock considerable trouble ^{was} experienced at the West Face.

At the East End the Rock was uniform and while considered Easy to Drill was thought to be difficult to Blast.

At the West End it was non uniform, ~~not~~ cleaved in places difficult to Drill in others and

9) This created several problems.

At the East End it was found that after being driven the Rock forming the sides and roof of the tunnel when exposed to the air tended to decay. Cracks and permit boulders to be come disengaged.

To eliminate this the Tunnel was Brick lined and this contract was given to B.H. Farren who effected an ~~arc~~ completed about 132 ft from Aug. to Nov.

During this year Mr Farren took the contract to complete the Arching of the West End.

In the mean time in order to solve some of the problems in the West End a shaft 314 ft deep 13 x 8 ft had been sunk between the Central shaft and the West End opening.

IT was decided to drive an adit or small Tunnel west from the shaft to ~~the~~ meet the

10) West end workings

The Tunnel ~~was~~ or adit was to be approximately 4ft high and 4ft wide and the contract was assumed by Mr Farren.

During this year Mr Doane resigned as chief engineer. ~~He~~ ~~was~~ as noted previously he was responsible for the original trials with Nitroglycerin and he also changed the methods which permitted the use of improvements in air and steam Drills.

The adoption of these methods later permitted obtaining the full effectiveness of Nitroglycerin.

after Mr Doane's resignation the work proceeded under Mr Alvah Crocker as Resident Commissioner until Oct 1967 when an accidental fire destroyed the Central Shaft Hoist and Shaft killing 13 men.

at this point the Contractors surrendered their contracts and

11) work stopped.

Mr Farren had completed an additional 350 ft of Brick lining, during this year.

On Jan 1 1968 when work was again proceeding on all faces it was noted that 509 men were being employed. about 2/3 of them in the troublesome west area.

During this year ~~the~~ a connection was made between the West shaft and the West End adit so now there was the free flow of water from the West shaft to the outside.

At this time arrangements had been made with Mr Mc Bray of North Adams to provide Witbrugger in and a new drilling system was developed to permit its effective use.

The original estimation stated that the ~~total~~ depth of the holes could be increased from 30 to 42 inches. and because of its greater strength and

12) shattering effect as compared to Black Powder. ~~the full depth~~ of the holes the rock was broken to the full depth of the holes where as previously 6" or more of Hole was often time left.

On Dec 24th 1968 it was decided to discontinue supervision by the state and a contract was let to Shanley Bros for approximately \$4,600,000 for completion of the Tunnel by Mar 1, 1974 with the possible option of 6 months additional.

It was estimated that up to Jan 1 1969 that the Tunnel had cost close to 3 Million Dollars so that now the Total cost would be \$7,600,000 as compared to the original estimation of 2 million.

On Jan 1 1969 all work had been suspended except the completion of Mr Farrells Contract.

B) Covering the Brick Arch on
the West End.

This was finished in Feb 1969
and this work taken over by
Shanley Bros in April.

Shanley Bros started working
in March and by Dec 1969 had
700 men on the Job.

In Aug 1970 as noted previously
the Central Shaft reached the
Tunnel level but because of the
necessary Trimming and Timbering
no advance ~~was made~~ on these
new faces was made until Oct.

On Oct 3d a heavy Rain storm
caused a creek adjacent to
the West End to overflow
the water reaching a height of
18ft above the arch.

The West End workings were
completely flooded and one man
was lost.

During 1970 the improvement in
Drills substitution of air for
steam for hand drilling saved
2/3 in the cost of this operation

14) During this year ¹⁸⁷² Nitroglycerin
was in general use, but
later a 75% Mixture with an
absorbent clay called Mica Powder
was used. in Reef and some
bottom holes.

It was noted that during the
next 5 years about 450,000 lbs
of Nitroglycerin and 100,000 lbs
of Mica Powder were used by
the Shanley Bros.

~~Work proceeded with the~~

Work now proceeded steadily
with the rate of progress
being increased as further
experience was gained with
~~more~~ the improved drills etc.

Finally on Dec 12 1872 the
East Heading met the one being
driven East from the Central shaft
and on Nov 27¹⁸⁷³ the West heading
met the one driven West.

Shanley Bros concluded their
contract Dec 22 1874 (about 4 months
late) but prior to this on Nov 19
the state had entered into a contract

15) With ^{considerable} B N Farren to do arching and enlarging not covered by the agreement. With Shanley.

Shanley was given ~~an~~ \$131,000 over their contract to pay for Flood Damage, additional arching required etc

This brought the ~~total~~ cost of the Tunnel to \$7,727,424.

Broken down to cover Mr Farrens work it was shown that he was paid 1,531,659 making the total \$9,258,563.

It was therefore assumed that the final cost of the Tunnel would be \$10,000,000 ~~and~~ with

A million addition being spent for 44 miles of Railroad including \$200,000 paid to Southern Vt railroad for their property.

14) The first Engine was run thru
Feb 9 1875

The first passenger train Oct 13
1875

The tunnel was declared
completed July 1 1876

Including ~~interest~~ the
approx. 3,300,00 interest
the total cost ~~was~~ Tunnel Project
was \$19,322,000

1876
1858

18

$\frac{A}{2}$

1876
2 - 9 $\frac{1}{4}$

~~1876~~

17 $\frac{1}{4}$
project

